# Bill of Quantities (BOQ)

## Civil Maintenance works of project period store with Steel Racks at KL3HPS

IFB No.: 151422/NEA-KL3-2083/084-CSQ-01

| Provisional Sum | | | | | |
|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Unit Rate (NPR)** | **Amount (NPR)** |
| PS.1 | provisional sum | PS | 1.00 | 0.00<br>Zero rupees only. | 0.00<br>Zero rupees only. |
| | **Total provisional sums** | | | | 0.00<br>Zero rupees only. |

| Civil Maintenanace Works | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.1 | Clearance of Scrap and others existing material, shifting materials from hulas store and proper arrangement of materials on the racks. | LS | 1.00 | | | |
| 2.1 | Fabrication of MS angle Rack, MS strip and Painting work as per instruction. | kg | 3,701.50 | | | |
| 2.2 | Fabrication of MS Circular pipe with primer as per instruction ,nominal bore 50mm(2.9mm thick) | kg | 327.81 | | | |
| 2.3 | Supplying and fitting of 19mm thick waterproof ply board at racks | Sq.m | 67.50 | | | |
| 2.4 | Supplying and fitting of Sheet metal (1.2mmthick) at racks | Kg | 212.00 | | | |
| 2.5 | Brick Masonry works in ground floor along with supplying bricks ,making cement sand mortar and construction of brick walls including haulage distance up to 30m.chimney Bhatta bricks in (1:4) cement /sand mortar. | Cu.m | 8.71 | | | |
| 2.6 | 12.50 mm thick cement/sand wall plastering work in 1:4 Cement / Sand mortar | Sq.m | 47.57 | | | |

| Civil Maintenanace Works | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 2.7 | Providing and painting two coats of interior distemper paint over one coat of interior primer on the plastered surface inside of wall. | Sq.m | 47.57 | | | |
| 2.8 | Supplying and fitting of 0.38mm (26 Guage medium) GI Sheet partition work including all complete | Sq.m | 63.00 | | | |
| 2.9 | Supplying and fitting of 26 gauge ridge cover colour sheet with 2 feet wide work including all complete | Rm | 21.45 | | | |

| | |
|---|---|
| **Total Item Price** | |
| VAT (13.00%) | |
| **Grand Total** | |